



P.O. Box 8747
Truckee, CA 96162

587-6070
CSL #507614
NSL #24406

PROPOSAL

DATE	ESTIMATE NO.
10/18/2009	1948

NAME / ADDRESS
Andy Sharp/Peter Sharp

JOB LOCATION
16004 Old Hwy Dr.

DESCRIPTION	TOTAL
<p>Tear Off existing roof and remove debris from premises. Install Vycor Ice & Water Shield entire roof. Double layer at eave line. Install 30# felt on entire roof. Eave and valley metal included. Replace and paint vent flashings. Composition shingles to be: 50yr Elk shingles. Install 3/8 CDX plywood over T&G if necessary. Cost \$4800.00. Repair all damaged T&G and beams as needed will be charged at \$75.00 per man hour plus material with a 2 man minimum. This bid is for heat trace on all edges with 2.5 feet spacing going up roof 4 feet. It includes cost of material and installation on roof with activation devices. It does not include the electrician who will have to look at the job and determine his cost for breakers and line voltage run to junction box with hook up to heat trace and activation devices. \$Cost material only \$5100.00. Cost of gutter and installation on front roof only with 2 downspouts. Cost \$1300.00. Install 2 inch nailable insulation board with 5/8 OSB already attached. This includes the 2x4 perimeter and 1x4 to cover the build up at edges. Total R-Value with total thickness of roof is about R-16. Price includes the cost of engineering. Cost \$10800.00. This proposal is only good for 30 days. Five year workmanship guarantee. Fully insured with Workers Comp and PL/PD Permit included. I agree to this proposal.</p> <p>Signed _____ Dated _____</p>	<p>15,600.00</p>
TOTAL	
	\$15,600.00

SIGNATURE _____